KADUR DIVISION.

The 26th July 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur division, up to 30th August 1897, for constructing a Taluk Cutcherry at Koppa. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Taluk Cutcherry at Koppa;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT ESTIMATE FOR CONSTRUCTING A TALUK CUTCHERRY AT KOPPA:

Items of work.	*Per.*	*Quantity.*
Earthwork excavation and filling the same earth for basement	C. yds.	441
Burnt stone in mortar for filling foundation with bond slabs	C. ft.	10,451
Do for basement do	"	3,521
Burnt brick in mortar for superstructure do	"	16,660
Do for archwork	"	1,117
Burnt stone slabs finely dressed for steps (6″ thick)	S. ft.	599
Do for lintels	"	119
Plastering with chunam	Sqr.	246·31
Color washing, 2 coats	"	85·68
Whitewashing do	"	170 82
Painting with chunam	"	12·53
Teakwood doors battened including frames ($3\frac{1}{2} \times 6\frac{1}{2}$) with iron work, rim, lock and key, &c.	S. ft.	569
Teakwood doors battened including frames ($3\frac{1}{2} \times 6\frac{1}{2}$) with iron work, rim, lock and key, &c., for treasury as per plan	"	23
Do windows battened and glazed including frame ($3\frac{1}{2} \times 4$) with iron work and iron bars, 1′ diameter ..	"	406
Do ventilator with glazed shutters including frame ($3\frac{1}{2} \times 2$) with iron work and iron bars $\frac{3}{4}$″ diameter.. ..	"	70
Do lower windows battened including frame ($2 \times 3\frac{1}{2}$) with iron work and iron bars 1″ diameter	"	14
Do entrance gate with strong iron work including frame ($6 \times 9\frac{1}{2}$) with lock and key as per plan	"	57
Do window for prisoners' room battened including frame ($3\frac{1}{2} \times 2\frac{1}{2}$) iron bars 1″ diameter and iron work and perforated zinc sheet	"	96
Brick in chunam column..	Lump sum.	
Chocolate painting for doors and windows	Sqr.	25·00
Teakwood railing between Treasury and Sheristadar's seat	S. ft.	45
Teakwood work	C. ft.	576·06
Do planking for lock-up rooms	S. ft.	636
Roofing with 1st class Mangalore tiles and teakwood reepers, &c., complete.	Sqr.	85·42
Ridging with Mangalore tiles set in mortar	R. ft.	396
Flat terrace to Treasury.	Sqr.	1·15
Bengal terrace to verandah	"	19 08
Flooring with burnt stone slabs and (6″) sand under the slab and cement painting	S. ft.	2,224
Do concrete (6″) and chunam plaster over it	C. ft.	1,372
Dental cornice work ornamental as per plan	R. ft.	174
Plain cornice	"	876
Do above plinth level	"	250
Ornamental finials	No.	4
Wood oiling..	Sqr.	40·00
Whiteant composition	"	20·00
Matting with bamboo outer rind	"	23·67
Zinc gutters for valley	R. ft.	50
Clearing site and sundries	Lump sum.	

The 26th July 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur division, up to 30th August 1897, for constructing Taluk Cutcherry at Balehonnur, Koppa taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Taluk Cutcherry at Balehonnur, Koppa taluk; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT ESTIMATE FOR CONSTRUCTING A TALUK CUTCHERRY AT BALEHONNUR, KOPPA TALUK.

Items of Work.	*Per.*	*Quantity.*
Earthwork excavation and filling the same earth for basement.. ..	C. yds.	441
Burnt stone in mortar for filling foundation with bond slabs	C. ft.	10,451
Do for basement do	,,	3,521
Burnt brick in mortar for superstructure do	,,	16,660
Do for archwork	,,	1,117
Burnt stone slabs finely dressed for steps (6" thick)	S. ft.	599
Do for lintels do	,,	119
Plastering with chunam	Sqrs.	246·31
Color washing, 2 coats	,,	85·68
Whitewashing do	,,	170·82
Painting with chunam	,,	12·53
Teakwood doors battened including frame ($3\frac{1}{2} \times 6\frac{1}{2}$) with iron work, rim, lock and key, &c.	S. ft.	569
Teakwood doors battened including frame ($3\frac{1}{2} \times 6\frac{1}{2}$) with iron work for Treasury rim lock and key, &c., as per plan	,,	23
Do windows battened and glazed including frame ($3\frac{1}{2} \times 4$) with iron work and iron bars 1" diameter	,,	406
Do ventilators with glazed shutters including frame ($3\frac{1}{2} \times 2$) with iron work and iron bars $\frac{3}{4}$" diameter.. ..	,,	70
Do lower windows battened including frame ($2 \times 3\frac{1}{2}$) with iron work and iron bars 1" diameter	,,	14
Do entrance gate with strong iron work including frame ($6 \times 9\frac{1}{2}$) with lock and key as per plan	,,	57
Do window of prisoners' room battened including frame ($3\frac{1}{2} \times 2\frac{1}{2}$) iron bars 1" diameter and iron works and perforated zinc sheet	,,	96
Brick in chunam column	Lump sum.	
Chacolate painting for doors and windows	Sqrs.	25·00
Teakwood railing between Treasury and Sheristadar's seat	,,	45
Teakwood work	C. ft.	576·06
Do planking for lock-up room	S. ft.	636
Roofing with 1st class Mangalore tiles and teak wood reepers, &c., complete.	Sqr.	85·42
Ridging with Mangalore tiles set in mortar	R. ft.	396
Flat terrace to Treasury	Sqr.	1·15
Bengal terrace to verandah	,,	19·03
Flooring with burnt stone slabs (6") sand under the slabs and cement painting	S. ft.	2,224
Do concrete (6") and chunam plaster over it	C. ft.	1,372
Dental cornice work ornamental as per plan	R. ft.	174
Plain cornice	,,	876
Do above plinth level	,,	260
Ornamental finials	No.	4
Wood oiling	Sqr.	40·00
Whiteant composition	,,	20·00
Matting with bamboo outer rind	,,	23·67
Zinc gutters for valley	R. ft.	50
Clearing site and sundries	Lump sum.	